



Community Investment Update

An update on the construction in your neighbourhood



Aberdeen Road and Hillside Drive Road Reconstruction

Notice Dated: November 11, 2024

PROJECT LOCATION:

Aberdeen Road (King Street to Hillside Drive) & Hillside Drive (Aberdeen Road to Ashby Drive)

PROJECT BACKGROUND

Aberdeen Road and Hillside Drive are rural boundary roads in Beamsville that have experienced increased traffic over the past several years as the community has grown. Increased levels of active transportation alongside deteriorating road conditions and increased vehicle volumes have triggered the need for comprehensive upgrades along these corridors. Our aim is to not only rebuild the roadways, but to enhance them to ensure optimal safety and functionality for all users, both now and in the foreseeable future.

PROJECT UPDATE

Rotomill has completed the Full Depth Reclamation with Expanded Asphalt Stabilization (FDR EAS) along Hillside Dr. and Aberdeen Rd. except for the closed area at the south end of Aberdeen. The contractor (Walker Construction) has paved both roads with base asphalt and is currently completing stormwater work near King Street, along with constructing armor stone retaining walls and concrete curbs. Temporary driveway transitions are now complete and will remain in place until spring, when permanent driveway restoration will be completed.

Please be advised that the section of road at the south end of Aberdeen Rd. will remain closed until Hydro One and the utility companies have completed their relocation works. Once complete, the contractor will proceed with constructing this last section of the roadway.

WHAT TO EXPECT NEXT

The contractor is scheduled to complete the following tasks by year-end:

- Ditching
- Shouldering
- Topsoil and Sod Restoration
- Line Painting

- Streetlight Installation

The following work is scheduled for **Spring 2025**:

- Topcoat Asphalt
- Speed Humps
- Permanent Line Painting
- Riprap Installation on the Slope
- Spillways
- Final Driveway Restorations

The contractor will provide a 24-hour notice for any disruptions of driveway access.

If you have any questions regarding the project, please contact one of the below team members:

CONTACT INFORMATION

Organization	Role	Contact Information
Town of Lincoln	Project Manager	Jemma Lynch Project Manager (905) 905-563-2799 ext. 264 jlynch@lincoln.ca
CIMA	Project Manager and Contractor Administration	Mike Murray P. Eng Senior Project Manager 289-288-0287 ext. 6836 murray@cima.ca

Speak Up Lincoln Webpage:



[Speakuplincoln.ca/aberdeen-road-reconstruction-project](https://speakuplincoln.ca/aberdeen-road-reconstruction-project)